

AD-A207 531

LITTLE DELL OUTLET STRUCTURE UTAH; HYDRAULIC MODEL  
INVESTIGATION(U) ARMY ENGINEER WATERWAYS EXPERIMENT  
STATION VICKSBURG MS HYDRAULICS LAB B P FLETCHER


1/1

UNCLASSIFIED


APR 89 MES/TR/HL-89-7

F/G 13/2

ML



NC




UTION TEST CHART



US Army Corps  
of Engineers

AD-A207 531



ONE FILE COPY

TECHNICAL REPORT HL-89-7

2

# LITTLE DELL OUTLET STRUCTURE, UTAH


## Hydraulic Model Investigation

by

Bobby P. Fletcher

Hydraulics Laboratory

DEPARTMENT OF THE ARMY  
Waterways Experiment Station, Corps of Engineers  
PO Box 631, Vicksburg, Mississippi 39181-0631



April 1989

Final Report

Approved For Public Release; Distribution Unlimited

DTIC  
ELECTE  
MAY 09 1989  
S E D

Prepared for US Army Engineer District, Sacramento  
Sacramento, California 95814-4794

89 5 03 013

Destroy this report when no longer needed. Do not return  
it to the originator.

The findings in this report are not to be construed as an official  
Department of the Army position unless so designated  
by other authorized documents.

The contents of this report are not to be used for  
advertising, publication, or promotional purposes.  
Citation of trade names does not constitute an  
official endorsement or approval of the use of  
such commercial products.

Unclassified

SECURITY CLASSIFICATION OF THIS PAGE

ADA207531

REPORT DOCUMENTATION PAGE				Form Approved OMB No. 0704-0188	
1a. REPORT SECURITY CLASSIFICATION Unclassified			1b. RESTRICTIVE MARKINGS		
2a. SECURITY CLASSIFICATION AUTHORITY			3. DISTRIBUTION / AVAILABILITY OF REPORT Approved for public release; distribution unlimited.		
2b. DECLASSIFICATION / DOWNGRADING SCHEDULE					
4. PERFORMING ORGANIZATION REPORT NUMBER(S) Technical Report HL-89-7			5. MONITORING ORGANIZATION REPORT NUMBER(S)		
6a. NAME OF PERFORMING ORGANIZATION USAEWES Hydraulics Laboratory		6b. OFFICE SYMBOL (If applicable) CEWES-HS-S	7a. NAME OF MONITORING ORGANIZATION		
6c. ADDRESS (City, State, and ZIP Code) PO Box 631 Vicksburg, MS 39181-0631			7b. ADDRESS (City, State, and ZIP Code)		
8a. NAME OF FUNDING / SPONSORING ORGANIZATION USAED, Sacramento		8b. OFFICE SYMBOL (If applicable)	9. PROCUREMENT INSTRUMENT IDENTIFICATION NUMBER		
8c. ADDRESS (City, State, and ZIP Code) 670 Capitol Mall Sacramento, CA 95814-4794			10. SOURCE OF FUNDING NUMBERS		
			PROGRAM ELEMENT NO.	PROJECT NO.	TASK NO.
			WORK UNIT ACCESSION NO.		
11. TITLE (Include Security Classification) Little Dell Outlet Structure, Utah; Hydraulic Model Investigation					
12. PERSONAL AUTHOR(S) Fletcher, Bobby P.					
13a. TYPE OF REPORT Final report		13b. TIME COVERED FROM _____ TO _____	14. DATE OF REPORT (Year, Month, Day) April 1989		15. PAGE COUNT 63
16. SUPPLEMENTARY NOTATION Available from National Technical Information Service, 5285 Port Royal Road, Springfield, VA 22161.					
17. COSATI CODES			18. SUBJECT TERMS (Continue on reverse if necessary and identify by block number)		
FIELD	GROUP	SUB-GROUP	Flood control; Plunge pool; Jet flow gates; Riprap		
19. ABSTRACT (Continue on reverse if necessary and identify by block number)					
<p>A 1:10-scale physical model of the discharge outlet, plunge pool, and exit channel was used to investigate and develop a practical design that would provide satisfactory hydraulic performance. Operation of the model with the original design indicated satisfactory performance in the conduits and jet flow gates. However, failure of the riprap in the plunge pool and exit channel was observed. The side slopes of the plunge pool and exit channel were modified to provide a stable environment for the riprap. <i>x y z d o.</i></p> <p><i>Sillings; Dam; energy dissipation;</i></p>					
20. DISTRIBUTION / AVAILABILITY OF ABSTRACT <input checked="" type="checkbox"/> UNCLASSIFIED/UNLIMITED <input type="checkbox"/> SAME AS RPT. <input type="checkbox"/> DTIC USERS			21. ABSTRACT SECURITY CLASSIFICATION Unclassified		
22a. NAME OF RESPONSIBLE INDIVIDUAL			22b. TELEPHONE (Include Area Code)		22c. OFFICE SYMBOL


DD Form 1473, JUN 86

Previous editions are obsolete.

SECURITY CLASSIFICATION OF THIS PAGE

Unclassified

SECURITY CLASSIFICATION OF THIS PAGE



SECURITY CLASSIFICATION OF THIS PAGE

# PREFACE

The model investigation was authorized by the Headquarters, US Army Corps of Engineers, on 14 September 1987, at the request of the US Army Engineer District, Sacramento. The studies were conducted by personnel of the Hydraulics Laboratory, US Army Engineer Waterways Experiment Station (WES), during the period September 1987 to June 1988 under the direction of Mr. F. A. Herrmann, Jr., Chief of the Hydraulics Laboratory, and under the general supervision of Messrs. G. A. Pickering, Chief of the Hydraulic Structures Division (HSD), and N. R. Oswalt, Chief of the Spillways and Channels Branch. Project engineer for the model study was Mr. B. P. Fletcher, assisted by Messrs. J. T. Hilbun, J. E. Hall, and J. R. Rucker, Jr., all of HSD. The model was constructed by Mr. W. Landers of the Engineering and Construction Services Division, WES. This report was written by Mr. Fletcher and edited by Mrs. M. C. Gay, Information Technology Laboratory, WES.

During the investigation, Messrs. Royce Cunningham, Harold Huff, and Charles Mifkovic, Sacramento District, visited WES to discuss the program of model tests and observe the model in operation.

COL Dwayne G. Lee, EN, is the Commander and Director of WES.  
Dr. Robert W. Whalin is the Technical Director.

Accession For	
NTIS GRA&I	<input checked="" type="checkbox"/>
DTIC TAB	<input type="checkbox"/>
Unannounced	<input type="checkbox"/>
Justification	
By	
Distribution/	
Availability Codes	
Dist	Avail and/or Special
A-1	






## CONTENTS

	<u>Page</u>
PREFACE.....	1
CONVERSION FACTORS, NON-SI TO SI (METRIC) UNITS OF MEASUREMENT.....	3
PART I: INTRODUCTION.....	5
The Prototype.....	5
Purpose and Scope of Model Study.....	8
PART II: THE MODEL.....	9
Description.....	9
Interpretation of Model Results.....	9
PART III: TESTS AND RESULTS.....	12
Jet Flow Gates.....	12
Discharge Conduits and Bifurcations.....	13
Plunge Pool and Exit Channel.....	13
PART IV: SUMMARY AND DISCUSSION.....	17
TABLES 1-5	
PHOTOS 1-4	
PLATES 1-16	

CONVERSION FACTORS, NON-SI TO SI (METRIC)  
UNITS OF MEASUREMENT

Non-SI units of measurement used in this report can be converted to SI  
(metric) units as follows:


<u>Multiply</u>	<u>By</u>	<u>To Obtain</u>
acre-feet	1,233.489	cubic metres
cubic feet	0.02831685	cubic metres
feet	0.3048	metres
inches	25.4	millimetres
miles (US statute)	1.609347	kilometres
pounds (mass)	0.4535924	kilograms
pounds (mass) per cubic foot	16.01846	kilograms per cubic metre



VICINITY MAP

SCALE

40 0 40 80 MI



LOCATION MAP

SCALE

2 0 2 4 MI



Figure 1. Location and vicinity map

## LITTLE DELL OUTLET STRUCTURE, UTAH

### Hydraulic Model Investigation

#### PART I: INTRODUCTION

##### The Prototype

1. The Little Dell Outlet Structure will be located about 8 miles\* east of Salt Lake City, UT (Figure 1). The proposed dam will be located on Dell Creek approximately 1.5 miles upstream from the existing Mountain Dell reservoir.

2. The project plan (Plate 1) provides for a rolled earth-fill dam embankment on Dell Creek to impound a 20,500-acre-ft reservoir. An ungated and unlined emergency spillway will be located on the right abutment. The outlet works will consist of a curved tunnel through the left abutment incorporating a midtunnel emergency control chamber located upstream of the dam axis. Operational control will be provided in the operational control structure located at the downstream tunnel portal. A plunge pool will dissipate the energy of released water, which will be returned to Dell Creek. A plan and profile of the recommended project and a plan of the operational control structure are shown in Plates 2 and 3, respectively.

3. The outlet works will have the multiple functions of (a) controlling flood-control and water quality releases from Little Dell Lake, and (b) conveying diverted waters from the Parleys Creek Diversion pipeline into Little Dell Lake. During flood-control operation, the 24-in.-diam water quality conduit and the 42-in.-diam Parleys Creek Diversion pipeline will normally be isolated from the 42-in.-diam flood-control conduit by closing valves located on these pipelines. Only reservoir releases through the flood-control conduit will be possible under these conditions. To make releases through the water quality system, the isolation valve on the flood-control conduit will be closed as well as the separation valve on the Parleys Creek Diversion pipeline. The valve on the water quality conduit will be opened and releases will

---

\* A table of factors for converting non-SI units of measurement to SI (metric) units is presented on page 3.

be made through the water quality conduit and the jet flow control gates. For diversion of Parleys Creek flows into Little Dell Lake, the 42-in. valves on the Parleys Creek Diversion pipeline and on the flood-control conduit will be opened. The valve on the water quality conduit will be closed. The jet flow control gates will be opened only enough to make small releases required downstream of the project. Parleys Creek Diversion flows exceeding downstream release requirements will be conveyed upstream through the outlet works conduit into Little Dell Lake. Once the release requirements exceed the diversion flow, the Parleys Creek Diversion pipeline will be shut. Schematic diagrams of the outlet works components are shown in Figure 2.

4. The outlet works (Plate 2) located through the left abutment will consist of a short approach channel, a submerged concrete intake structure, 320 ft of 6-ft-diam circular cut-and-cover concrete conduit, 340 ft of 6-ft-diam circular tunnel, an 84-ft-long emergency control chamber, 1,230 ft of 42-in.-diam steel conduit housed in a 9.5-ft-diam modified circular tunnel adit, bifurcations to two 36-in.-diam steel conduits each transitioning to a 30-in. diameter and having a 30-in.-diam emergency ball valve and 30-in.-diam jet flow gate for controlling releases, and a 20-ft-deep preformed plunge pool.

5. Outlet works releases will be controlled using jet flow gates. Two 30-in.-diam. jet flow gates will be located at the outlet of each 30-in.-diam steel conduit (Plate 3). The jet flow gates will have a design discharge of 370 cfs and discharge directly to the atmosphere. The fundamental features of the jet flow gates are a truncated conical nozzle, a floating seal ring that forms a circular discharge orifice at the downstream end of the nozzle, and a flat-bottomed gate leaf that contacts and slides across the seal ring orifice to regulate discharges. The basic features produce a contracted, jet-type discharge from the gate resulting in a discharge coefficient of approximately 0.83 at full gate openings and reduced cavitation potential. Jet flow gates were selected over other types of control gates or valves because of the jet flow gates' superior performance under winter icing conditions, low fabrication cost, and cavitation-free operation. A 30-in.-diam full port ball valve will be located approximately 15 ft upstream of each jet flow gate. These ball valves will serve as guard valves for the jet flow gates and will be operated only in the full open or full closed position.

6. The outlet works conduit will terminate with the 30-in.-diam jet







Figure 2. Normal gate and valve operation

flow control gates. Outlet works releases will discharge directly to the atmosphere immediately downstream of the gate orifice. The center-line elevation of the jet flow gates will be 5,575.0.\* A short section of steel pipe will function as a hood or deflector for spray at partial gate openings. The discharge jet will be fully aerated downstream of the jet flow gate. Outlet works releases will exit the jet flow gates in a semicylindrical form and will fall in approximately parabolic paths into a preformed plunge pool.

7. Outlet works releases will return to Dell Creek downstream of the plunge pool via an excavated trapezoidal exit channel. The channel will have an 8-ft bottom width and side slopes of 1V on 2H. The channel invert will intersect the plunge pool at el 5,558.5. The exit channel will be approximately 275 ft long with a bottom slope of 0.0060. The channel invert and side slopes will be protected with a layer of rock riprap 18 in. thick. The exit channel will have subcritical flow for the entire range of expected discharges. Where the exit channel intersects the natural streambed, the flow regime will change from subcritical to supercritical. A terminal structure, consisting of 10 ft of concrete-lined channel with cutoff walls, will be provided to prevent head cutting and excessive erosion.

#### Purpose and Scope of Model Study

8. The model study was conducted to evaluate the potential for cavitation in the discharge conduits, the hydraulic characteristics of the plunge pool and exit channel, and the size and extent of riprap required for protection of the plunge pool and exit channel, and to develop practical modifications required (if needed) for a satisfactory design.

9. Tests were conducted in the 1:10-scale model to evaluate single and multiple gate operation for various anticipated flow conditions.

---

\* All elevations (el) cited herein are in feet referred to the National Geodetic Vertical Datum (NGVD).

## PART II: THE MODEL

### Description

10. The model of the Little Dell outlet works (Figures 3 and 4), constructed to a scale ratio of 1:10, included 60 ft of the 3.5-ft-diam conduit upstream of the bifurcation, the bifurcation, the conduits to the jet flow gates, the jet flow gates, the plunge pool, a 300-ft length of the exit channel, and the terminal structure at the downstream end of the exit channel.

11. The conduits and jet flow gates were constructed of transparent plastic to permit observation of dye injected into the flow. Piezometers were installed in the conduits to permit measurement of pressures at critical locations. The plunge pool and exit channel were molded with graded riprap to simulate prototype riprap construction. The terminal structure at the downstream end of the exit channel was constructed of plywood.

12. Water used in operation of the models was supplied by pumps, and discharges were measured by orifice meters.

### Interpretation of Model Results

13. The accepted equations of hydraulic similitude based upon Froude criteria were used to express the mathematical relations between the dimensions and hydraulic quantities of the model and prototype. The general relations expressed in terms of the model scale or length ratio  $L_r$  are presented in the following tabulation:

<u>Dimension</u>	<u>Ratio</u>	<u>Scale Relations Model:Prototype</u>
Length	$L_r = L_r$	1:10
Area	$A_r = L_r^2$	1:100
Velocity	$V_r = L_r^{1/2}$	1:3.16
Time	$T_r = L_r^{1/2}$	1:3.16
Discharge	$Q_r = L_r^{5/2}$	1:316.2
Pressure	$P_r = L_r$	1:10
Weight	$W_r = L_r^3$	1:1,000






Figure 3. Plunge pool and exit channel



Figure 4. Discharge conduits  
and jet flow gates

14. Measurement of each of the dimensions or variables can be transformed quantitatively from model to prototype equivalents by these scale relations.

# PART III: TESTS AND RESULTS

## Jet Flow Gates

15. The outlet works including piezometer locations and the jet flow gates are shown in Plate 4. Model tests were conducted to calibrate the two identical jet flow gates for various gate openings, discharges, and heads. A sketch of one of the jet flow gates used in the model is shown in Plate 5. The test results permitted development of an equation by plotting discharge through jet flow gate 1 versus the energy head  $H_{01}$  on the center line of the discharge conduit at  $P_1$  (Plate 4) and then plotting the constants for the equation in Plate 6 versus percent jet flow gate opening (Plate 7). The energy head ( $H_{01}$  and/or  $H_{02}$ ) at  $P_1$  and/or  $P_2$  was obtained by subtracting the head loss  $H_\ell$  from the vertical distance between the upper pool elevation and the elevation of the center line of the discharge conduits at  $P_1$  and  $P_2$  (el 5,575). The head loss values furnished by the US Army Engineer District, Sacramento, are shown in the following tabulation.

Discharge Q cfs	Head Loss $H_\ell$ ft
150	26.7
200	47.5
250	74.3
300	106.9
370	162.7

For identical gate openings and discharges, the heads at  $P_1$  and  $P_2$  were identical. Therefore, the following equations can be used for determining, for gate 1, gate 2, or both gates, the relative values of discharge, head, and percent gate opening:

$$Q_t = Q_1 + Q_2 \quad (1)$$

$$Q_t = 0.80(2g)^{1/2} \left[ \left( \frac{A_{01}}{A_{T1}} \right)^{0.15} A_{01} H_{01}^{1/2} + \left( \frac{A_{02}}{A_{T2}} \right)^{0.15} A_{02} H_{02}^{1/2} \right] \quad (2)$$

where

- $Q_t$  = total discharge (gate 1 + gate 2), cfs
- $Q_1$  = discharge for gate 1, cfs
- $Q_2$  = discharge for gate 2, cfs
- $g$  = acceleration due to gravity,  $\text{ft/sec}^2$
- $A_{01}$  = area of gate 1 opening, sq ft
- $A_{T1}$  = area of gate 1 full open, sq ft
- $H_{01}$  = energy head upstream of gate 1, ft
- $A_{02}$  = area of gate 2 opening, sq ft
- $A_{T2}$  = area of gate 2 full open, sq ft
- $H_{02}$  = energy head upstream of gate 2, ft

#### Discharge Conduits and Bifurcations

16. Tests were conducted to investigate the potential for cavitation in the two 36-in.-diam conduits and bifurcations. Average hydrostatic pressures in the discharge conduits and bifurcations were measured by piezometers. Piezometers were located in critical areas (Plate 4) to identify zones of potential cavitation. Pressures measured for various upper pool elevations are tabulated in Table 1. The upper pool elevation was simulated in the model by simulating the energy head (pressure head  $H_p$  + velocity head  $H_v$ ) at  $P_1$  and/or  $P_2$  (Plate 4). The pressures in Table 1 are all positive and indicate that the discharge conduits and bifurcations will not be subject to cavitation.

#### Plunge Pool and Exit Channel

17. Tests were conducted to evaluate riprap stability in the plunge pool and exit channel. Details of the original design plunge pool and exit channel are shown in Plate 8. The plunge pool and exit channel were lined with riprap and subjected to various flow releases from the jet flow gates with upper pool elevations of 5,685, 5,750, 5,798 and 5,810. The upper pool elevations were simulated in the model by setting the pressure head  $H_p$  at  $P_1$  and/or  $P_2$  (Plate 4).  $H_p$  was determined by the following equation:

$$H_p = \text{Pool El} - \phi \text{ Outlet El} - H_L - H_v \quad (3)$$

where

‡ Outlet El = 5,575

$H_l$  = calculated head loss from intake to cross section where  $H_p$  was measured

$H_v$  = velocity head at cross section where  $H_p$  was measured

For each test, the riprap was subjected to a constant hydraulic condition for a period of 3 hr (prototype), and then the plunge pool and exit channel were drained and inspected for riprap displacement.

Original design (type 1  
plunge pool and exit channel)

18. Initially the plunge pool and exit channel were lined with 18-in. riprap (Figure 3). The prototype riprap gradation limits and the riprap gradation simulated in the model for the 18-in. riprap (Figure 3) are shown in Plate 9. The gradation curves in Plate 9 indicate that the model riprap gradation was designed to be conservative. The riprap used in the model had a unit weight of 160 pcf. If the proposed prototype rock has a different unit weight than the rock used in the model, then the thickness of the prototype riprap  $T_2$  should be adjusted by the following equation:

$$T_2 = \frac{T_1}{\left( \frac{\gamma_{s2} - \gamma_w}{\gamma_w} \right) \left( \frac{\gamma_{s1} - \gamma_w}{\gamma_w} \right)} \quad (4)$$

where

$T_2$  = thickness required in prototype, in.

$T_1$  = thickness simulated in model, in.

$\gamma_{s2}$  = unit weight of riprap to be used in prototype, pcf

$\gamma_w$  = unit weight of water in prototype, pcf

$\gamma_{s1}$  = unit weight of riprap used in model, pcf

19. Various flow conditions with a single gate and both gates operating are shown in Photo 1. Hydraulic parameters, including the percentage gate opening  $G_o$ , and whether or not failure occurred are shown. Typical riprap failure zones are illustrated in Photo 2. Sketches indicating failure zones

and distance from gate to impact zone are shown in Plate 10. Wave heights (amplitudes) measured in the locations shown in Plate 11 are tabulated in Table 2. Various flow conditions with riprap stability characteristics indicated are tabulated in Table 3.

20. In areas where failure occurred, the 18-in. riprap was replaced with 24-in. riprap (type 2 riprap design) as shown in Plate 12. The riprap gradation simulated in the model for the 24-in. riprap is shown in Plate 13. Tests indicated that the 24-in. riprap also failed under similar hydraulic conditions in the areas where the 18-in. riprap had failed.

Recommended design (type 2 plunge pool and exit channel) and type 3 riprap design

21. The plunge pool and exit channel were revised to provide flatter side slopes as shown in Plate 14 (type 2 plunge pool and exit channel). The plunge pool and exit channel were lined with 18-in. riprap as shown in Figure 5. Various flow conditions are illustrated in Photo 3. Riprap stability characteristics for various flow conditions are tabulated in Table 4. The 18-in. riprap was stable for all flow conditions except for a




Figure 5. Type 2 plunge pool and exit channel

flow of 150 cfs through jet flow gate 1 with a pool el 5,798.0. The area where the riprap was displaced is shown in Photo 4 and Plate 15. The 18-in. riprap was replaced with 24-in. riprap in the area shown in Plate 16 (type 3 riprap design). Riprap stability characteristics for various flow conditions are tabulated in Table 5. Wave heights (amplitudes) measured in the locations shown in Plate 11 are tabulated in Table 2. Although the wave heights were consistently higher with the type 2 plunge pool, the magnitude of the wave height was not severe with either of the designs. The type 2 plunge pool and exit channel and type 3 riprap design were subjected to various anticipated flow conditions and satisfactory energy dissipation with no riprap displacement observed.

#### PART IV: SUMMARY AND DISCUSSION

22. Model tests conducted to calibrate the jet flow gates permitted the development of an equation relating the following parameters: (a) discharge, (b) head on center line of gate, and (c) gate opening. The equation can be used for determining, for gate 1, gate 2, or both gates, the relative values of discharge, head, and percent gate opening.

23. Tests were conducted to investigate the potential for cavitation in the bifurcations and the two 36-in.-diam conduits for various heads and flow rates. The pressures measured by piezometers were positive and indicate that the outlet works should not be subject to cavitation.

24. Riprap failure was observed in the original design plunge pool and exit channel for numerous anticipated flow conditions with single or multiple gate operation. The geometry of the plunge pool and exit channel was modified (type 2 plunge pool and exit channel) to provide flatter side slopes more conducive to riprap stability. The revised design was stable for all anticipated flow conditions except for one area of 18-in. riprap that failed with 150 cfs passing through a single gate. The area of 18-in. riprap that failed was replaced with 24-in. riprap (type 3 riprap design). The type 2 plunge pool and exit channel lined with the type 3 riprap design (Plate 16) was subjected to various anticipated flow conditions, and no riprap failure was observed.



Table 1  
Pressures in Little Dell Outlet Works

Pressures in Prototype Feet of Water					
Piezometer* No.      El		Discharge Gate 1 203 cfs Gate 2 203 cfs Pool El 5,810 Gate Opening 100%	Discharge Gate 1 185 cfs Gate 2 185 cfs Pool El 5,810	Discharge Gate 1 150 cfs Gate 2 150 cfs Pool El 5,740	Discharge Gate 1 100 cfs Gate 2 100 cfs Pool El 5,665
1	5,575.00	23±2	63±2	52	41
2	↓	12±2	49±2	42±2	38
3		19±2	56±2	46±2	42
4		13±2	48±2	42	38
5		18±2	54±2	44	39
6		22±2	57±2	49±2	42
7		26±7	62±8	52±5	43±3
8		22±3	57±3	47±2	42±2
9	5,576.25	38±4	79±4	61±3	47±3

\* Piezometer locations are shown in Plate 4.

Table 2  
Wave Heights

Pool El	Discharge, cfs	Gate Opening percent		Wave Height, ft, for Location*				
		Gate 1	Gate 2	1	2	3	4	5
<u>Type 1 Plunge Pool and Exit Channel Design</u>								
<u>Type 1 Riprap Design</u>								
<u>(Original Design)</u>								
5,685	150	57	--	0.2	0.3	0.5	0.4	0.4
5,685	150	--	57	0.3	0.5	0.5	0.5	0.5
5,798	300	49	49	0.4	1.0	1.2	1.0	0.5
5,798	150	39	--	0.5	0.7	1.0	1.0	0.7
5,798	150	--	39	0.2	0.5	1.2	0.7	0.4
5,810	370	77	77	0.4	1.2	1.5	1.5	1.1
<u>Type 2 Plunge Pool and Exit Channel Design**</u>								
<u>Type 3 Riprap Design</u>								
<u>(Recommended Design)</u>								
5,685	150	57	--	0.7	0.8	0.9	0.8	0.6
5,685	150	--	57	0.8	0.9	0.9	0.9	0.8
5,798	300	49	49	0.6	1.2	1.3	1.3	0.8
5,798	150	39	--	0.7	1.0	1.3	1.4	1.0
5,798	150	--	39	0.4	0.7	1.3	1.0	0.7
5,810	370	77	77	0.5	1.4	1.7	1.7	1.4

\* See Plate 11.

\*\* See Plate 16.

Table 3  
Riprap Stability Characteristics  
Type 1 Plunge Pool and Exit Channel Design  
18-in. Riprap

Pool El	Discharge, cfs		Gate Opening, percent		Riprap Failure	
	Gate 1	Gate 2	Gate 1	Gate 2	No	Yes
5,685	50	--	20	--	x	
	150	--	57	--		x
	--	50	--	20	x	
	--	150	--	57		x
	50	50	20	20	x	
	75	75	31	31	x	
5,740	50	--	16	--		x
	150	--	46	--		x
	--	150	--	16	x	
	--	150	--	46		x
	50	50	17	17	x	
	75	75	25	25	x	
	150	150	66	66	x	
5,798	50	--	14	--	x	
	150	--	39	--		x
	--	50	--	14	x	
	--	150	--	39		x
	50	50	15	15	x	
	75	75	21	21		x
	150	150	49	49		x
5,810	185	185	77	77		x
	203	203	100	100	x	

Note: Test duration 3 hr (prototype).

Table 4  
Riprap Stability Characteristics  
Type 2 Plunge Pool and Exit Channel Design  
18-in. Riprap

Pool El	Discharge, cfs		Gate Opening, percent		Riprap Failure	
	Gate 1	Gate 2	Gate 1	Gate 2	No	Yes
5,685	50	--	20	--	x	
	150	--	57	--	x	
	--	50	--	20	x	
	--	150	--	57	x	
	50	50	20	20	x	
	75	75	31	31	x	
5,740	50	--	16	--	x	
	150	--	46	--	x	
	--	50	--	16	x	
	--	150	--	46	x	
	50	50	17	17	x	
	75	75	25	25	x	
	150	150	66	66	x	
5,798	50	--	14	--	x	
	150	--	39	--		x
	--	50	--	14	x	
	--	150	--	39	x	
	50	50	15	15	x	
	75	75	21	21	x	
	150	150	49	49	x	
5,810	185	185	77	77	x	
	203	203	100	100	x	

Note: Test duration 3 hr (prototype).


Table 5  
Riprap Stability Characteristics  
Type 2 Plunge Pool and Exit Channel Design  
Type 3 Riprap Design  
18- and 24-in. Riprap

Pool El	Discharge, cfs		Gate Opening, percent		Riprap Failure	
	Gate 1	Gate 2	Gate 1	Gate 2	No	Yes
5,685	50	--	20	--	x	
	150	--	57	--	x	
	--	50	--	20	x	
	--	150	--	57	x	
	50	50	20	20	x	
	75	75	31	31	x	
5,740	50	--	16	--	x	
	150	--	46	--	x	
	--	50	--	16	x	
	--	150	--	46	x	
	50	50	17	17	x	
	75	75	25	25	x	
5,798	150	150	66	66	x	
	50	--	14	--	x	
	150	--	39	--	x	
	--	50	--	14	x	
	--	150	--	39	x	
	50	50	15	15	x	
5,810	75	75	21	21	x	
	150	150	49	49	x	
	185	185	77	77	x	
	203	203	100	100	x	

Note: Test duration 3 hr (prototype).



- a. Pool el 5,685, gate 1 discharge 50 cfs and opening 20 percent, gate 2 closed, no rock failure after 3 hr operation (prototype)




- b. Pool el 5,685, gate 1 closed, gate 2 discharge 150 cfs and opening 57 percent, rock failure after 3 hr operation (prototype)

Photo 1. Various flow conditions, type 1 plunge pool and exit channel (Sheet 1 of 6)



c. Pool el 5,685, gate 1 discharge 50 cfs and opening 20 percent, gate 2 discharge 50 cfs and opening 20 percent, no rock failure after 3 hr operation (prototype)



d. Pool el 5,740, gate 1 discharge 50 cfs and opening 17 percent, gate 2 discharge 50 cfs and opening 17 percent, no rock failure after 3 hr operation (prototype)



e. Pool el 5,740, gate 1 discharge 150 cfs and opening 66 percent, gate 2 discharge 150 cfs and opening 66 percent, no rock failure after 3 hr operation (prototype)



f. Pool el 5,798, gate 1 closed, gate 2 discharge 50 cfs and opening 14 percent, no rock failure after 3 hr operation (prototype)






g. Pool el 5,798, gate 1 discharge 50 cfs and opening 14 percent, gate 2 closed, no rock failure after 3 hr operation (prototype)



h. Pool el 5,798, gate 1 closed, gate 2 discharge 150 cfs and opening 39 percent, rock failure after 3 hr operation (prototype)



- i. Pool el 5,798, gate 1 discharge 150 cfs and opening 39 percent, gate 2 closed, rock failure after 3 hr operation (prototype)



- j. Pool el 5,798, gate 1 discharge 50 cfs and gate opening 15 percent, gate 2 discharge 50 cfs and gate opening 15 percent, no rock failure after 3 hr operation (prototype)



k. Pool el 5,798, gate 1 discharge 150 cfs and opening 49 percent, gate 2 discharge 150 cfs and opening 49 percent, rock failure after 3 hr operation (prototype)



l. Pool el 5,810, gate 1 discharge 185 cfs and gate opening 77 percent, gate 2 discharge 185 cfs and gate opening 77 percent, rock failure after 3 hr operation (prototype)



a. Pool el 5,798, gate 1 discharge 150 cfs and opening 39 percent, gate 2 closed, after 3 hr operation (prototype)



b. Pool el 5,798, gate 1 discharge 150 cfs and opening 49 percent, gate 2 discharge 150 cfs and opening 49 percent, after 3 hr operation (prototype)

Photo 2. Typical failure zones, type 1  
plunge pool and exit channel



a. Pool el 5,685, gate 1 discharge 50 cfs and opening 20 percent,  
gate 2 closed



b. Pool el 5,685, gate 1 discharge 150 cfs and opening 57 percent,  
gate 2 closed

Photo 3. Various flow conditions, type 2 plunge pool and  
exit channel (Sheet 1 of 9)



c. Pool el 5,740, gate 1 discharge 50 cfs and opening 16 percent,  
gate 2 closed



d. Pool el 5,740, gate 1 discharge 150 cfs and gate opening 46 percent,  
gate 2 closed



e. Pool el 5,798, gate 1 discharge 50 cfs and opening 14 percent,  
gate 2 closed



f. Pool el 5,798, gate 1 discharge 150 cfs and opening 39 percent,  
gate 2 closed



g. Pool el 5,685, gate 1 closed, gate 2 discharge 50 cfs and opening 20 percent



h. Pool el 5,685, gate 1 closed, gate 2 discharge 150 cfs and gate opening 57 percent





i. Pool el 5,740, gate 1 closed, gate 2 discharge 50 cfs and opening 16 percent




j. Pool el 5,740, gate 1 closed, gate 2 discharge 150 cfs and gate opening 46 percent



k. Pool el 5,798, gate 1 closed, gate 2 discharge 50 cfs and opening 14 percent



l. Pool el 5,798, gate 1 closed, gate 2 discharge 150 cfs and opening 39 percent




m. Pool el 5,685, gate 1 discharge 50 cfs and opening 20 percent, gate 2 discharge 50 cfs and opening 20 percent



n. Pool el 5,740, gate 1 discharge 50 cfs and opening 17 percent, gate 2 discharge 50 cfs and opening 17 percent



o. Pool el 5,740, gate 1 discharge 150 cfs and opening 66 percent, gate 2 discharge 150 cfs and gate opening 66 percent



p. Pool el 5,798, gate 1 discharge 50 cfs and opening 15 percent, gate 2 discharge 50 cfs and opening 15 percent



q. Pool el 5,798, gate 1 discharge 150 cfs and opening 49 percent, gate 2 discharge 150 cfs and opening 49 percent



r. Pool el 5,810, gate 1 discharge 203 cfs and opening 100 percent, gate 2 discharge 203 cfs and gate opening 100 percent



Photo 4. Riprap failure, view from downstream, type 2 plunge pool and exit channel, 18-in. riprap, gate 1 discharge 150 cfs and opening 39 percent, gate 2 closed, pool el 5,798, test duration 3 hr (prototype)



# PROJECT PLAN






PLATE 2









PLAN

NOTE: ALL PIEZOMETERS ARE LOCATED ON THE SIDE OF CONDUIT ON THE  $\phi$  EXCEPT PIEZOMETER NO. 9. PIEZOMETER NO. 9 IS LOCATED ON TOP OF THE CONDUIT.  
 ① INDICATES PIEZOMETER NUMBER.


## PIEZOMETER LOCATIONS






**JET FLOW GATE**



DISCHARGE PER GATE VERSUS HEAD ON  
CENTER LINE OF DISCHARGE CONDUIT



CONSTANT VERSUS RATIO OF ORIFICE  
AREA TO AREA OF FULL GATE OPENING



**SECTION A-A**

**SCALE**

10 0 10 20 FT


## TYPICAL EXIT CHANNEL SECTION

SCALE

10 0 10 20 FT

**PLUNGE POOL AND EXIT  
CHANNEL  
SECTIONS AND DETAILS  
ORIGINAL DESIGN**

RIPRAP GRADATION  
18 INCH



	JET FLOW GATE 1	JET FLOW GATE 2
GATE OPENING		57%
DISCHARGE		150 CFS



**LEGEND**

 FAILURE

**RIPRAP FAILURE  
ORIGINAL DESIGN**



	JET FLOW GATE 1	JET FLOW GATE 2
GATE OPENING	57%	
DISCHARGE	150 CFS	



**SCALE**

20 0 20 40 FT




	JET FLOW GATE 1	JET FLOW GATE 2
GATE OPENING		39%
DISCHARGE		150 CFS



PLATE 10  
(SHEET 3 of 6)

DURATION OF TESTS 3 HR  
POOL EL 5798

	JET FLOW GATE 1	JET FLOW GATE 2
GATE OPENING	39%	
DISCHARGE	150 CFS	




LEGEND  
FAILURE

RIPRAP FAILURE  
ORIGINAL DESIGN

DURATION OF TESTS 3 HR  
POOL EL 5798

	JET FLOW GATE 1	JET FLOW GATE 2
GATE OPENING	49%	49%
DISCHARGE	150 CFS	150 CFS




**LEGEND**  
 FAILURE

**RIPRAP FAILURE**  
ORIGINAL DESIGN


DURATION OF TESTS 3 HR  
POOL EL 5810

	JET FLOW GATE 1	JET FLOW GATE 2
GATE OPENING	77%	77%
DISCHARGE	185 CFS	185 CFS




LEGEND  
 FAILURE


RIPRAP FAILURE  
ORIGINAL DESIGN



LOCATION OF WAVE HEIGHT MEASUREMENTS  
ORIGINAL DESIGN




TYPE 2 RIPRAP DESIGN  
TYPE 1 PLUNGE POOL




RIPRAP GRADATION  
24 INCH









END

FILMED

6-89

DTIC